CHARGE ATLAS / RONALD REAGAN

Ronald Reagan H-E-B | Four-post investigation | Not investment-ready

Unchanged policy: base payback <=6 years; conservative <=8 years from first spend; base NPV >=0 at 10% real over 10 operating years; positive conservative cash and all six evidence gates.

19348 Ronald W. Reagan Blvd, Georgetown, TX 78628

Assumption / evidence status	What the crosscheck establishes	Unresolved
59 paid sessions per day Unverified high-demand target	59 sessions on four posts = 14.75/post/day. The remote five-post example becomes 47.2/day when normalized to four posts; retaining 59 requires 25% more throughput per post. Sources 1 / 2	Nearby paid histories, $0.51 price-matched demand and queue losses.
35 billed kWh per session Plausible externally; unverified locally	EV-ChART federal totals imply about 37.81 kWh/session. This supports 35 as a sensitivity input; it does not verify the local paid mean or vehicle mix. Sources 1 / 2	Local billed-energy distribution and paid share.
150 kW established 4CP Technically conceivable; not assured	At assumed 15% losses, a permanent 150 kW cap needs 16.20 full-power hours/day, or 95.27% of a 17-hour window. Targeted summer curtailment is a different design; neither control nor retained sales is assured. Sources 1 / 2	Tesla/PEC meter-control terms, cost and performance.
Complete project and operating cost Scope clearer; complete quote missing	Local 2021 construction registrations: $160k Cedar Park, $315k Georgetown. They exclude specified cost categories and are not current four-post all-in quotes. Sources 1 / 2 / 3	Complete EPC, PEC CIAC, land, taxes and control package.

Five nearby operating comparisons. Operator pages verify supply, not paid orders. Distances are straight-line from the retained AFDC inventory; no matched local paid history was obtained.

Comparator / address	Miles	Published equipment	Transfer limitation
Whitestone Market / H-E-B Tesla 2800 E Whitestone Blvd, Cedar Park, TX 78613	7.3	11 Tesla posts; up to 325 kW; 24/7 Sources 1	Same grocery/Tesla setting, but 11 versus four posts; no paid history.
Cedar Park Town Center Tesla 1001 E Whitestone Blvd, Cedar Park, TX 78613	7.4	12 Tesla posts; up to 250 kW; 24/7 Sources 1	Larger established retail site; this is not the separate planned Cypress Creek location.
EVgo The Parke 5001 183A Frontage Road, Cedar Park, TX 78613	6.8	4 stalls: two 100 kW units plus a shared 350 kW dual unit Sources 1	Comparable stall count; different network, connectors and shared power.
EVgo Cedar Park 700 E Whitestone Blvd, Cedar Park, TX 78613	7.6	4 stalls; four 100 kW units Sources 1	Comparable stall count; slower equipment and another network.
Georgetown Wolf Ranch Tesla 1015 W University Ave, Georgetown, TX 78628	7.8	16 Tesla posts; up to 250 kW; 24/7 Sources 1	Larger retail/interstate catchment; no local billing or energy history.

Nearby H-E-B engineering plan: 11 posts, three cabinets and transformer foundation, plus ADA/civil work. PEC tie-in remains marked pending in that historical plan; no complete price or Ronald capacity is established. Sources 1

CHARGE ATLAS / CONDITIONAL ECONOMICS

Ronald Reagan H-E-B | Four-post investigation | Not investment-ready

Unchanged policy: base payback <=6 years; conservative <=8 years from first spend; base NPV >=0 at 10% real over 10 operating years; positive conservative cash and all six evidence gates.

59-session target rebased into three scenarios. All use 35 billed kWh/session and $0.51/kWh realized price. The 70% / 100% / 120% demand factors are author-selected stresses, not probabilities. Monthly peak 600 kW and established 4CP 150 kW are separate assumptions. Conservative utility components are stressed +25%; construction/ramp/replacement inputs are retained.

Scenario	Sessions / site / day	Gross capex	Payback from first spend / NPV	Decision
Conservative	41.3	$634.5k	No recovery* NPV -$424.9k	Fails <=8-year downside rule
Base	59.0	$564.0k	4.67 yr NPV $347.9k	Conditional only; no evidence admission
Optimistic	70.8	$517.0k	3.01 yr NPV $818.8k	Conditional only; no evidence admission

Combined gate: FAIL. A positive base target does not clear the conservative payback rule. Sensitivities hold other base inputs fixed; port-normalized rows combine the stated session and energy assumptions.

Sensitivity around the 59-session base	Value / interpretation	Payback / NPV
Five-post example normalized to four posts	47.2 sessions/day x 22 kWh	No recovery* / -$333.8k
Five-post example normalized to four posts	47.2 sessions/day x 35 kWh	6.07 yr / $73.7k
1 of four summer peaks at 600 kW	4CP 262.5 kW; annual TCOS $19.2k	4.80 yr / $308.6k
2 of four summer peaks at 600 kW	4CP 375.0 kW; annual TCOS $27.5k	4.95 yr / $269.4k
4 of four summer peaks at 600 kW	4CP 600.0 kW; annual TCOS $44.0k	5.29 yr / $190.8k
Unquoted additional gross capital +$100.0k	Total $664.0k	5.28 yr / $239.5k
Unquoted additional gross capital +$200.0k	Total $764.0k	5.90 yr / $131.1k

4CP rows repeat the specified summer average each established year; they do not predict miss probability or a one-time event. One missed peak adds $8,248.50/year TCOS at the published rate. The 47.2-session transfer is illustrative, not a forecast.

Cost boundary. No complete design-matched quote was obtained. The $564,000 base is the retained $470,000 vendor reference plus an unallocated $94,000 allowance, not a priced scope ledger. Nearby public registrations improve scope awareness, but their historical construction estimates exclude specified categories and cannot replace a 2026 four-post third-party budget. Newly identified fees are not added twice to an unallocated allowance. Known small fees: $175 accessibility filing and $120 for four initial port registrations, where applicable; RAS and renewal costs remain separate.

Still unpriced: complete civil/electrical/ADA/drainage EPC; PEC CIAC and service equipment; rent/access; tax and insurance; control/storage and lost sales; recurring obligations and removal. Obtain matching contracts and quotes before admission.

USD, pre-tax/unlevered. NPV uses 10% real discount and 10 operating years; no residual/grant/growth. * No recovery within construction plus 10 operating years. Utility subtotals omit unresolved charges; missing costs may lower returns. Full 18-case analysis and acquisition paths are linked below.