CHARGE ATLAS / TEN FOLLOW-UP PRIORITIES

The same ten properties | Two investigation perspectives | 0 qualified / 37 pending

Unchanged policy: base payback <=6 years; conservative <=8 years from first spend; base NPV >=0 at 10% real over 10 operating years; positive conservative cash and all six evidence gates.

Qualitative investigation priorities within the existing 37-property pool. The network and third-party orders rank the same selected ten. They are not return rankings, investment qualifications, measured probabilities or a nationwide optimum.

Location / scope / order	Why follow up	Verify next / downgrade or stop
1. H-E-B at Ronald Reagan Blvd 19348 Ronald W. Reagan Blvd, Georgetown, TX 78628 New-build hypothesis Network #4 / Third-party #1	The most testable conditional model in this pool. Nearby comparisons and explicit demand, price, peak-control and cost sensitivities make the next evidence consequential. 59 paid sessions/day is still unverified.	Confirm owner/H-E-B parking authority; obtain price-matched paid transactions from nearby operators, PEC meter/tariff/capacity terms, Tesla control performance, and a complete matching EPC/connection/site quote. Stop / downgrade: Do not upgrade if verified demand and complete costs fail the joint downside/base gates. A favorable base target alone is insufficient.
2. WinCo Foods Puyallup 9518 176th Street East, Puyallup, WA 98375 New-build / phased-build hypothesis Network #5 / Third-party #2	24-hour retail and a retained nearest-DCFC distance of 4.1 straight-line miles justify a bounded tariff/control and demand inquiry. Parcel and PSE evidence offer concrete next steps.	Confirm the PSE meter, eligible tariff, actual program availability and peak-control design; then test paid demand and full costs for a smaller phased project. Stop / downgrade: Ordinary tariff economics may fail. Do not assume preferential electricity or maximum rebates; pause paid design if the complete bill and paid demand fail the unchanged gates.
3. Elgin H-E-B 1080 West Hwy 290, Elgin, TX 78621 New-build corridor hypothesis Network #2 / Third-party #5	US 290 corridor: one DCFC record within ten miles in the retained supply snapshot. Potential incremental network value merits an access and utility check.	Identify the actual Oncor/Bluebonnet meter; resolve highway right-of-way and driveway plans before estimating passing-EV capture, paid volume and connection cost. Stop / downgrade: Downgrade if access is impaired or supply removes the incremental need. Do not transfer PEC tariffs to this property.
4. WinCo Foods Oregon City 19701 Highway 213, Oregon City, OR 97045 New-build hypothesis Network #7 / Third-party #3	The retained nearest DCFC is 4.2 straight-line miles away. AMCAP's May 2026 site plan provides a specific parking/management discussion basis, not granted site rights.	Confirm AMCAP/WinCo parking authority and the actual meter; obtain utility capacity, time-of-use/demand billing and full construction scope, then validate paid demand. Stop / downgrade: Marketing traffic is not charging orders. Exclude unawarded PGE support; stop if rights or the complete verified case cannot support the joint gates.
5. Hannaford #8128 149 Dublin Street, Machias, ME 04654 Canceled-project restart hypothesis Network #3 / Third-party #7	A canceled same-address project and a current Phase 12 town-eligible RFP make restart and equipment eligibility decisive questions. No site award or Tesla compatibility has been established.	Ask Hannaford/the prior operator and Efficiency Maine to resolve cancellation, existing rights, Tesla hardware/protocol compliance and reimbursement conditions. Published deadline: April 30, 2027, 23:59 Eastern. Stop / downgrade: No compliant Tesla route means no Tesla Supercharger recommendation; a generic DCFC award is not interchangeable. Unawarded support is sensitivity only.

Priorities approved October 30, 2026, using retained public evidence. Supply distances and record counts are from the October 29 snapshot, are straight-line rather than driving distances, and do not prove demand. This is not a new nationwide supply scan or ten completed commercial reviews.

All ten remain pending. No evidence gate, payback threshold, financial input or qualification decision changes in this release. Ronald retains the v0.9 conditional tests; no unsupported new payback estimates were created for the other nine.

CHARGE ATLAS / TEN FOLLOW-UP PRIORITIES

The same ten properties | Two investigation perspectives | 0 qualified / 37 pending

Unchanged policy: base payback <=6 years; conservative <=8 years from first spend; base NPV >=0 at 10% real over 10 operating years; positive conservative cash and all six evidence gates.

Qualitative investigation priorities within the existing 37-property pool. The network and third-party orders rank the same selected ten. They are not return rankings, investment qualifications, measured probabilities or a nationwide optimum.

Location / scope / order	Why follow up	Verify next / downgrade or stop
6. H-E-B Mansfield 1670 E Broad St, Mansfield, TX 76063 New-build hypothesis; competition first Network #8 / Third-party #4	A named property filing and utility route make follow-up actionable. The nearby 1715 E Broad charging project is a potentially decisive counterexample to the early network thesis.	Verify current operation, power, pricing and queues at 1715 E Broad before H-E-B/Oncor design work. It is across from 1670 E Broad, not the same parcel. Obtain actual meter and connection terms. Stop / downgrade: Downgrade if nearby supply meets demand without demonstrated overflow. Gas-generator nameplate power does not prove spare charging capacity.
7. WinCo Foods Edmonds 21900 Highway 99, Edmonds, WA 98026 Expansion / redesign only Network #9 / Third-party #6	An existing EVgo operator and historical charging plans create identifiable routes to throughput, asset and rights evidence. This is an incremental project, not an empty parking lot.	Confirm WinCo/EVgo exclusivity and expansion rights, incremental paid demand, reusable asset condition and a complete incremental investment quote. Stop / downgrade: Pause without expansion rights or new demand. Use incremental cash flows; existing station revenue cannot all be credited to new investment.
8. LaPerle's IGA 64 Trooper Leslie Lord M Highway, Colebrook, NH 03576 Recovery / upgrade only Network #6 / Third-party #8	NHEC's historical announcement names ReVision Energy and a battery-integrated charger, providing a route to operating and meter records. Current availability remains unresolved.	Request current status, downtime cause, paid logs, battery/meter intervals, asset/data rights and replacement costs from ReVision, the host and NHEC. Stop / downgrade: An installation announcement is not uptime evidence. Without a lawful takeover/cooperation route, retain as a comparator rather than a development site.
9. Lamb's Market 911 South US Highway 93, Challis, ID 83226 New-build corridor hypothesis Network #1 / Third-party #10	US 93 retail node with a retained nearest-DCFC gap of 67.7 straight-line miles. Network coverage is a stronger hypothesis than investment returns; merchant address evidence exists.	Reconcile the street address, map entrance and parcel; verify 24-hour parking, actual utility, year-round passing EVs, winter paid demand and connection costs. Stop / downgrade: A large gap is not paid demand. Pause if seasonal demand and grid costs cannot satisfy the same investment gates; network priority grants no exemption.
10. WinCo Foods Medford 251 E Barnett Rd, Medford, OR 97501 Canceled-project recovery / redesign only Network #10 / Third-party #9	Cancellation records and a Pacific Power planning/upgrade route justify checking asset reuse. Nearby DCFC supply about 0.2 straight-line miles away limits the incremental thesis.	Resolve cancellation causes, existing rights, reusable civil/electrical works, Tesla eligibility and complete incremental costs before evaluating a restart. Stop / downgrade: Do not present this as an ordinary greenfield recommendation while cancellation, rights and incremental demand remain unresolved.

Priorities approved October 30, 2026, using retained public evidence. Supply distances and record counts are from the October 29 snapshot, are straight-line rather than driving distances, and do not prove demand. This is not a new nationwide supply scan or ten completed commercial reviews.

All ten remain pending. No evidence gate, payback threshold, financial input or qualification decision changes in this release. Ronald retains the v0.9 conditional tests; no unsupported new payback estimates were created for the other nine.